

Full equipment and ergonomic arrangement of devices will allow you to move into the home immediately.

PUR foam insulation of 18 cm covering the steel structure in combination with underfloor heating will ensure constant, optimal temperature inside the mobile home.

High-class finishing materials give the interiors a luxurious character. Elegance while practicality of the materials used.

JB MOON LIGHT PREMIUM MOBILE HOME



4,3 m

Photos are illustrative photos and are not the subject of the offer. Other options





JB MOON LIGHT



	External dimensions	17.77
	Weight	13,33 m x 4,26 m
	Height of rooms	14 tonnes
	Useful Area:	
	Useful Area:	45,34 m² (living room combined with kitchenette: 14,93 m², bathroom: 3,32 m², large bedroom: 7,53 m², small bedroom 1: 5,96 m²,
	Construction	small bedroom II: 4,52 m², corridor: 9,08 m² + 1,69 m² terrace)
	Construction	Steel frame with wooden elements, made on the basis of a structural design with 4 wheels, including two swivel wheels. Rigid axle
		+ swivel. Galvanised undercarriage construction, rodent-proofing. Convertible drawbar from front to rear for moving the house.
	Floor	The model has 8 support points. 8 galvanised steel supports included.
	Roof/ceiling	In addition to the steel structure, waterproof plywood, 18 cm PUR open-cell foam, wooden substructure, OSB board and vinyl panel.
	Kool/ cening	In addition to the steel structure elements, timber substructure, 18 cm PUR open cell foam, high vapour permeable membrane, OSB
		board, roof covered with aluminium roof system. Raised ceiling throughout the bungalow, covered with timber boarding, ceiling in
	External walls	the bathroom - Fibo system.
	External wans	Aluminium façade system. In addition to steel construction elements, wooden substructure, OSB board, insulation in the form of 18
		cm PUR open-cell foam, membrane (wind-barrier) and vapour-barrier foil. Interior cladding MDF panel with Fibo system decorative elements.
	Internal walls	Wooden structure, OSB board, covered with MDF panel, partition walls soundproofed with 5 cm mineral wool. Interior cladding
	Internal wans	MDF panel with decorative elements of the Fibo system in the hall, walls in the bathroom - Fibo system.
	Doors	Entrance 90/200 cm single-leaf PVC door with high quality finish surface, veneered on the outside, with glazing in a 3-pane
	20013	package; internal 70/200 cm white MDF door.
	Windows	7/6-chamber system, installation depth: 80 mm, triple-glazed packet with steel frame, PVC profiles with high-quality finishing
	THILDOWS	surface in veneer on the outside, glazed showcase with sliding door option to fit within a 3,7 m x 2,8 m outline. Dimensions may
		differ from actual dimensions ± 5 cm.
	Electrical installation	Distribution box, 3-phase installation. Electrical conduits in peszel. For sockets 3x2,5mm2, for lighting 3x1,5mm2. Electrical sockets,
		USB sockets (x5), aerial (x1), internet (x1) and light switches. Sockets outside and under the bungalow.
	Plumbing installation	Plumbing in the kitchen and bathroom made of ALU-PEX and PVC pipes. Hidden in the walls and routed under the bungalow for
	J	connection to the mains.
	Ventilation	Venting of the sanitary installation, two-stage continuous exhaust ventilation with wall fan located in the bathroom, ventilators with
		heater.
	Ligtening inside	Interior lighting: Ceiling-mounted adjustable LED spots in each room, preparation for pendant lamps to be installed by the client,
		additional linear LED lighting in the living room, bathroom, and above the beds in the bedrooms. Outdoor lighting: directional
		sconces, illumination of the glazed showcase with waterproof LED linear lighting. LED lighting switched on from a remote control.
	Heating	Underfloor heating throughout the bungalow in the form of a heating film adapted to work under the floor panel, working with
		wi-fi enabled controllers. Additionally an electric ribbed radiator in the bathroom.
	Bathroom	Square corner shower cubicle 90 x 90 cm, wall mounted cabinet with mirrored fronts and LED linear lighting, pedestal washbasin
		with cabinet in which the boiler has been placed. Cabinet top made of HPL. Suspended toilet bowl.
	Kitchen	Kitchen furniture finished with furniture board in white gloss and woodgrain, large built-in fridge, telescopic hood, 4-burner
		induction hob, oven with microwave function, stainless steel inset sink, dishwasher and washing machine placed in the kitchen
		island. Countertop and walls in the kitchen made of HPL compact board.
	Living room	Sofa bed, space for TV/aerial socket, air conditioning, space for round table with chairs.
	Large bedroom	Double bed 140/200 cm with exchangeable spring mattress and bedding container, wardrobe with hinged doors (bar, shelves),
		and in part with mirrored fronts, bedside table (x2), row of wall units above the bed, upholstered panels, headboard wall finished
		with furniture board.
	Small bedroom II	Single bed 80/200 cm with exchangeable spring mattress and bedding container, wardrobe with hinged doors (bar, shelves),
		and with mirrored fronts, bedside table, row of wall units above the bed, upholstered panels, headboard wall finished with furniture
		board.
	Corridor	Seat with shoe cupboard, and a sequence of wall cabinets in recess, upholstered panels over seat, recess finished with furniture
		board, three storage cupboards, one with mirrored sides.

Mobile Homes Manufacturer

Letniskowo sp. z o.o. Ul. Elewatorska 29, 15-620 Białystok KRS 0001024501, NIP 5423465217, REGON 524717637 www.jbhomes.uk www.new-static-caravans.uk

> export@letniskowo.pl +48 667 580 099